

**Florida Building Code Product Approval**  
**FL10185.5-R3 Non Impact- 12'0" x 24" Transom DP75**

FL #	FL10185-R3
Application Type	Revision
Code Version	2010
Application Status	Approved
	*Approved by DBPR. Approvals by DBPR shall be reviewed and ratified by the POC and/or the Commission if necessary.
Comments	
Archived	<input type="checkbox"/>
Product Manufacturer	Nan Ya Plastics Corporation USA
Address/Phone/Email	8989 North Loop East Houston, TX 77029 (713) 674-7822 Ext 105 ajen96@yahoo.com.tw
Authorized Signature	RUSKIN WU ajen96@yahoo.com.tw
Technical Representative	Ruskin Wu
Address/Phone/Email	8989 North Loop East Houston, TX 77029-1217 (713) 674-7822 Ext 105 ajen96@yahoo.com.tw
Quality Assurance Representative	
Address/Phone/Email	
Category	Windows
Subcategory	Fixed
Compliance Method	Certification Mark or Listing
Certification Agency	National Accreditation & Management Institute
Validated By	National Accreditation & Management Institute,

# Florida Building Code Product Approval

## FL10185.5-R3 Non Impact- 12'0" x 24" Transom DP75

FL #	Model, Number or Name	Description
10185.5	GTO 12020 GLAZED TRANSOM	GTO 12020 GLAZED TRANSOM VINYL FIXED WINDOW
<b>Limits of Use</b> Approved for use in HVHZ: No Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +75/-75 Other:		<b>Certification Agency Certificate</b> <a href="#">FL10185 R3 C CAC NI006564-R3.pdf</a> <b>Quality Assurance Contract Expiration Date</b> 02/28/2016 <b>Installation Instructions</b> <a href="#">FL10185 R3 II 08-01973.pdf</a> Verified By: Luis Roberto Lomas 62514 Created by Independent Third Party: Yes <b>Evaluation Reports</b> <a href="#">FL10185 R3 AE 512683.pdf</a> Created by Independent Third Party: Yes

# Florida Building Code Product Approval

## FL10185.5-R3 Non Impact- 12'0" x 24" Transom DP75

### NOTICE OF PRODUCT CERTIFICATION



CERTIFICATION NO: NI006564-R2  
 DATE: 05/25/2006  
 CERTIFICATION PROGRAM: Structural  
 COMPANY: Nan Ya  
 CODE: 661-1  
 REVISION DATE: 03/27/2013

To verify that the "Notice of Product Certification" is valid, please visit [www.NAMICertification.com](http://www.NAMICertification.com) to assure that the product is active and currently listed. This certification represents product conformity to the applicable specification and that certification criteria has been satisfied. A NAMI approved certification label must be applied to the product to claim certification status. Please review and advise NAMI if any corrections are required to this document.

COMPANY NAME AND ADDRESS	PRODUCT DESCRIPTION
<p>Nan Ya Plastics/Plastpro, Inc.                      8989 North Loop East                      Houston, TX 77029</p>	<p>Series "GTO 12020"                      Glazed Transom Vinyl Fixed Window</p> <p>Configuration: OOO                      Glazing: Insulating Glass (Tempered)</p> <p>Frame: W-3692mm(145.38") H-610mm(24")                      DLO: W-1179mm(46.4") H-536mm(21")</p>

SPECIFICATION	PRODUCT RATING
<p>AAMA/WDMA 101/I.S.2/A440-05                      ASTM F588-04</p>	<p>TR-R75                      FER-Passed</p>

Product Tested By: Architectural Testing, Inc.  
 Report No: 62724.01-801-44  
 Expiration Date: February 28, 2016

Administrator's Signature: \_\_\_\_\_ 

**NATIONAL ACCREDITATION AND  
 MANAGEMENT INSTITUTE, INC.**  
 4794 George Washington Memorial Highway  
 Hayes, VA 23072  
 Tel: (804) 684-5124  
 Fax: (804) 684-5122

# Florida Building Code Product Approval

## FL10185.5-R3 Non Impact- 12'0" x 24" Transom DP75

*L. Roberto Lomas P.E.*

1432 Woodford Rd.  
Lewisville, NC 27023  
336-945-9695  
rlomas@lrlomaspe.com

### Engineering Evaluation Report

Report No.: 512683

**Manufacturer:** Nan Ya Plastics Corporation  
8989 North Loop East  
Houston, TX 77029

**Product Line:** GTO 12020 Glazed Transom Vinyl Fixed Window

**Compliance:**

The above mentioned product has been evaluated for compliance with the requirements of the Florida Department of Community Affairs for Statewide Acceptance per Rule 9N-3.005 method 1(a). The product listed herein complies with requirements of the Florida Building Code.

**Supporting Technical Documentation:**


1. Approval document: drawing number 08-01973, titled GTO 12020 Glazed Transom Vinyl Fixed Window, prepared, signed and sealed by Luis Roberto Lomas P.E.
2. Report No.: ATI-62724.01-801-44 signed by Andy Cost  
Architectural Testing Inc., Southlake, TX  
AAMA/WDMA/CSA 101/I.S.2/A440-05  
Design pressure:  $\pm 75.0$ psf  
Water penetration resistance 11.28psf
3. Anchor calculations, report number 512683-1, prepared, signed and sealed by Luis Roberto Lomas P.E.

**Limitations and Conditions of use:**

- Maximum design pressure:  $\pm 75.0$ psf (GTO 12020)
- Maximum unit size: 145" x 24" (GTO 12020)
- Units must be glazed per ASTM E 1300-04, see installation instructions for glass options.
- This product is not rated to be used in the HVHZ.
- This product is not impact resistant and requires impact protection in wind borne debris regions.
- Frame material to be foam PVC.

**Installation:** Units must be installed in accordance with approval document, 08-01973.

**Certification of Independence:** Please note that I don't have nor will acquire a financial interest in any company manufacturing or distributing the product(s) for which this report is being issued. Also, I don't have nor will acquire a financial interest in any other entity involved in the approval process of the listed product(s).



REVISIONS			
REV	DESCRIPTION	DATE	APPROVED


NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH REQUIREMENTS OF THE FLORIDA BUILDING CODE.
2. WOOD FRAMING AND MASONRY OPENING TO BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO STRUCTURE. FRAMING AND MASONRY OPENING IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
3. 1X BUCK OVER MASONRY/CONCRETE IS OPTIONAL. WHERE 1X BUCK IS NOT USED DISSIMILAR MATERIALS MUST BE SEPARATED WITH APPROVED COATING OR MEMBRANE. SELECTION OF COATING OR MEMBRANE IS THE RESPONSIBILITY OF THE ARCHITECT OR ENGINEER OF RECORD.
4. ALLOWABLE STRESS INCREASE OF 1/3 WAS NOT USED IN THE DESIGN OF THE PRODUCT SHOWN HEREIN. WIND LOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
5. FRAME MATERIAL: EXTRUDED RIGID FOAM PVC.
6. UNITS MUST BE GLAZED PER ASTM E1300-04, SEE SHEET 2 FOR GLASS OPTIONS.
7. APPROVED IMPACT PROTECTIVE SYSTEM IS REQUIRED FOR THIS PRODUCT IN WIND BORNE DEBRIS REGIONS.
8. SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM. SHIM WHERE SPACE OF 1/16" OR GREATER OCCURS. MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4".
9. FOR ANCHORING INTO WOOD FRAMING OR 2X BUCK USE #10 WOOD SCREWS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 3/8" MINIMUM EMBEDMENT INTO SUBSTRATE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
10. FOR ANCHORING INTO MASONRY/CONCRETE USE 3/16" TAPCONS WITH SUFFICIENT LENGTH TO ACHIEVE A 1 1/4" MINIMUM EMBEDMENT INTO SUBSTRATE WITH 2 5/8" MINIMUM EDGE DISTANCE. LOCATE ANCHORS AS SHOWN IN ELEVATIONS AND INSTALLATION DETAILS.
11. ALL FASTENERS TO BE CORROSION RESISTANT.
12. INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BELOW:
  - A. WOOD - MINIMUM SPECIFIC GRAVITY OF G=0.42
  - B. CONCRETE - MINIMUM COMPRESSIVE STRENGTH OF 3,192 PSI.
  - C. MASONRY - STRENGTH CONFORMANCE TO ASTM C-90, GRADE N, TYPE 1 (OR GREATER).
13. TRANSOM UNITS MAY BE INSTALLED VERTICALLY OR HORIZONTALLY.


SIGNED: 03/25/2013

TABLE OF CONTENTS	
SHEET NO.	DESCRIPTION
1 - 2	ELEVATIONS AND NOTES
3	INSTALLATION DETAILS

NAN YA PLASTICS CORP. USA 8989 NORTH LOOP EAST HOUSTON, TX 77029		
GTO 12020 GLAZED TRANSOM VINYL FIXED WINDOW NOTES		
DRAWN: V.L.	DWG NO. 08-01973	REV -
SCALE NTS	DATE 03/22/13	SHEET 1 OF 3




REVISIONS			
REV	DESCRIPTION	DATE	APPROVED




**GTO 1200 GLAZED TRANSOM**  
EXTERIOR VIEW

DESIGN PRESSURE RATING	IMPACT RATING
±75.0PSF	NONE



**GLAZING DETAIL**




**MULLION DETAIL**


NAN YA PLASTICS CORP. USA  
8989 NORTH LOOP EAST  
HOUSTON, TX 77029

GTO 1200 GLAZED TRANSOM  
VINYL FIXED WINDOW  
ELEVATION AND DETAILS


DRAWN: V.L.	DWG NO. 08-01973	REV -
SCALE NTS	DATE 03/22/13	SHEET 2 OF 3



REVISIONS			
REV	DESCRIPTION	DATE	APPROVED



**HORIZONTAL CROSS SECTION**  
**2X BUCK/WOOD FRAMING INSTALLATION**  
**JAMB SHOWN HEAD AND SILL SIMILAR**



**HORIZONTAL CROSS SECTION**  
**MASONRY/CONCRETE INSTALLATION**  
**JAMB SHOWN HEAD AND SILL SIMILAR**

NAN YA PLASTICS CORP. USA 8989 NORTH LOOP EAST HOUSTON, TX 77029		
GTO 12020 GLAZED TRANSOM VINYL FIXED WINDOW INSTALLATION DETAILS		
DRAWN: V.L.	DWG NO. 08-01973	REV -
SCALE NTS	DATE 03/22/13	SHEET 3 OF 3

